

SECTION 14
1:20 S103

100 THICK SPRAYED
CONCRETE WALL



STRIP CORE DRAIN (TO BE
DISCONTINUOUS LOCALLY AT
BORED PIERS)

PROVIDE 2-N16 DOWELS FROM
SUSPENDED SLAB INTO EACH
BORED PIER, 600 LONG OVERALL,
EPOXY GROUTED 250 INTO
BORED PIER

BP5
Ø600 BORED PIER @
1050 C/C MAX

VIEW FROM ARROW 'Y'

1:20

AA	FOR CONSTRUCTION	OG	FK	19.10.18
No	REVISION	DRAWN	CHEKD	DATE
PROJECT THE WILLCOX APARTMENTS AT: 117 PROSPECT ROAD PROSPECT, SA 5082 FOR: CITIFY & BFC PTY LTD				
DRAWING TITLE				
SECTIONS & DETAILS				
<div> <div> Civil Environmental Mechanical Fire Lifts </div> <div> Structural Geotechnical Electrical Hydraulics Green ESD </div> <div>  </div> </div> <p>Level 6, 100 Pirie Street, Adelaide SA 5000 Telephone 08 8238 4100 Facsimile 08 8410 1405</p>				
SCALES <div> <div>AS SHOWN</div> <div>  COPYRIGHT RESERVED </div> </div>				
DRAWN		DRAWING No.		
DATE		1802052-S407/AA		
ENGINEER				
CHECKED				