



NOTE:
ALL SEWER AND TRADE WASTE PIPEWORK SHALL BE
INSTALLED AT THE FOLLOWING MINIMUM GRADES
UNLESS OTHERWISE STATED:
• $\phi 40 - \phi 65$: 2.50% MINIMUM
• $\phi 100$: 1.65% MINIMUM
• $\phi 150$: 1.00% MINIMUM
ALL VENT PIPEWORK SHALL BE INSTALLED AT 125%
MINIMUM GRADE UNLESS OTHERWISE STATED.

CONSTRUCTION ISSUE

A		CONSTRUCTION ISSUE	21.09.18	AS
REV	NO	DESCRIPTION	DATE	CHK'D
LUCID CONSULTING AUSTRALIA Level 3/169 Pirie St Adelaide SA 5000 Phone: (08) 8407 9700 Email: adelaide@lucidconsulting.com.au				
CLIENT CITIFY bfc				
PROJECT THE WILLCOX APARTMENTS 117 PROSPECT ROAD, PROSPECT				
DRAWING BASEMENT SANITARY DRAINAGE ARRANGEMENT				
HYDRAULIC SERVICES				
SCALE 1:100@A1		DATE SEPTEMBER 2018		
DESIGNED JZ		DRAWN JZ/ML		No. IN SET 2 OF 17
DRAWING NUMBER LCE13523-H02		REVISION A		